

**BID FORM (continued)**

Francis Budin  
Storage and Treatment Wetland

REVISED 4/17/2020

The undersigned offers to furnish labor, materials and equipment necessary to complete the project in accordance with the project plans, specifications and bid schedule, at the unit prices and/or amount specified.

NAME: <u>Barnett Bros Inc.</u>
SIGNATURE: <u>Jim Walker</u>
DATE: <u>5-22-2020</u>

Notes:

All sales tax paid by the contractor in securing product for this bid shall be included as part of the total bid price.

- (A) Tie all joints.
- (B) Cellular confinement system shall consist of EnviroGuard EGA20 with 6-inch deep cells. See special provisions for material and installation specifications.
- (CV) Compacted Volume
- (P) Plan Quantity for which no direct measurement shall be made.

(end of bid form)

BBI

**BID FORM**  
Francis Budin  
Storage and Treatment Wetland

REVISED 4/17/2020

Item No.	Item Description	Pay Unit	Estimated Quantity	Unit Price	Bid Amount
1	MOBILIZATION	L.S.	1	500.00	500.00
2	CLEAR AND GRUB TREES IN WORK AREA	L.S.	1	1,100.00	1,100.00
3	MOW VEGETATION IN WORK AREA	ACRES	2.7	100.00	270.00
4	REMOVE AND DISPOSE OF EXISTING CMP CULVERTS AND METAL APRONS (approx. 24 LF - 24" and 48 LF - 18")	L.S.	1	500.00	500.00
5	SALVAGING & SPREADING TOPSOIL Includes: (approx. 500 cy at embankment, 400 cy at borrow)	C.Y.	900 (CV/P)	4.00	3,600.00
6	COMMON EXCAVATION (CV) Includes: (core trench, removing existing driveway, placing excavated material on proposed embankment sideslopes)	C.Y.	890 (CV/P)	4.00	3,560.00
7	CLAY BORROW (CV) - CLASS 'C' COMPACTION Includes: (driveway embankment, core trench)	C.Y.	1210 (CV/P)	4.00	4,840.00
8	GRANULAR BEDDING (CV)	C.Y.	18 (CV)	25.00	450.00
9	FURNISH & INSTALL 30 IN. DIA. REINFORCED CONCRETE PIPE APRON	EACH	1	900.00	900.00
10	FURNISH & INSTALL 30 IN. DIA. REINFORCED CONCRETE PIPE	L.F.	100 (A)	90.00	9,000.00
11	FURNISH & INSTALL OUTLET CONTROL STRUCTURE	EACH	1	7,000.00	7,000.00
12	GEOTEXTILE FABRIC (MNDOT TYPE 4)	S.Y.	107	2.00	214.00
13	FURNISH & INSTALL RIPRAP (MNDOT CLASS III)	TONS	65	70.00	4,550.00
14	AGGREGATE SURFACING, CLASS 5	TONS	144	20.00	2,880.00

(continued)

BBI

**BID FORM (continued)**Francis Budin  
Storage and Treatment Wetland

REVISED 4/17/2020

Item No.	Item Description	Pay Unit	Estimated Quantity	Unit Price	Bid Amount
15	EARTHWORK - WETLAND SCRAPE & FLATTEN DITCH SIDE SLOPES	C.Y.	817 (CV/VP)	4.00	3268.00
16	FURNISH & INSTALL FLAP GATE FOR 18-INCH GMP Includes: (remove apron, 8 ft cmp extension, connecting band, flap gate)	L.S.	1	1000.00	1000.00
17	SEDIMENT CONTROL LOG, TYPE COMPOST	L.F.	200	3.50	700.00
18	FERTILIZER, TYPE 3 (22-5-10 ANALYSIS)	LBS	200	1.00	200.00
19	SEEDING	ACRES	3.8	125.00	475.00
20	SEED MIX 21-112 (WINTER WHEAT COVER CROP)	LBS	170	1.50	85.00
21	SEED MIX 25-141 (MESIC GENERAL ROADSIDE)	LBS	9	4.00	36.00
22	SEED MIX 33-261 (STORMWATER SOUTH AND WEST)	LBS	14	30.00	420.00
23	SEED MIX 35-241 (MESIC PRAIRIE)	LBS	57	20.00	1140.00
24	MULCH MATERIAL, TYPE 1 (DISK-ANCHORED)	TONS	8	100.00	800.00
25	EROSION CONTROL BLANKET, CATEGORY 3N	S.Y.	420	2.00	840.00
26	TURF REINFORCEMENT MAT, MNDOT CATEGORY 3	S.Y.	420	9.00	3780.00
27	FURNISH & INSTALL CELLULAR CONFINEMENT SYSTEM	S.Y.	80	32.00	2560.00

TOTAL BID PRICE (Total of all Bid Amounts):

54,668.00

(continued)

### COOPERATOR'S REVIEW AND APPROVAL STATEMENT

I have reviewed the plans and specifications and agree to complete the work accordingly. Modification of these plans and specifications must be approved by the South Central Technical Service Area before installation. Failure to meet these plans and specifications may jeopardize my State or Federal cost-share funding.

I am responsible for clearly locating and marking all private utilities and tile lines within the work area. Failure to locate and mark private utilities and tile lines may increase my construction costs. I am responsible for securing all necessary permits and completing the work in accordance with all Local, State, and Federal Laws. I am responsible for all negotiations and agreements with the contractor(s). I will be available during construction to discuss potential modifications and conduct necessary negotiations with the contractor(s).


\_\_\_\_\_  
(Cooperator's Signature)

\_\_\_\_\_  
(Date)

### CONTRACTOR'S REVIEW AND APPROVAL STATEMENT

I have reviewed the plans and specifications and agree to complete the work accordingly. Modification of these plans and specifications must be approved by the owner and the South Central Technical Service Area before installation. Failure to meet these plans and specifications may jeopardize the owner's State or Federal cost-share funding.

I understand that before the start of construction, the owners of all utilities must be notified. The excavator is responsible for giving this notice by calling the "Gopher State One Call" system at 1-800-252-1166 or at [www.gopherstateonecall.org](http://www.gopherstateonecall.org) at least 48 hours prior to any excavation.

  
(Contractor's Signature)

\_\_\_\_\_  
5-22-2020  
(Date)